RENCANA ANGGARAN BIAYA

PEKERJAAN : PENANAMAN POHON PENEDUH CLUSTER BUKIT SAKURA

LOKASI : CLUSTER BUKIT SAKURA - CITRAINDAH CITY

NO	URAIAN	SAT	VOLUME	HARSAT		JUMLAH	KETERANGAN
l.	Dakariaan Baraianan						
 	Pekerjaan Persiapan Pembuatan lubang tanam (0.5x0.5x0.5m) AREA 1	ttk	106,00	30.000	Rp	3.180.000	
2	Pembuatan lubang tanam (0.5x0.5x0.5m) AREA 1 Pembuatan lubang tanam (0.5x0.5x0.5m) AREA 2	ttk	67.00	30.000	Кр	2.010.000	
	Pembuatan lubang tanam (0.5x0.5x0.5m) AREA 3	ttk	98,00	30.000	Rp	2.940.000	
4	Top soil (pupuk + tanah merah + sekam + pasir) AREA 1	m3	13,25	220.000	Rp	2.915.000	
5	Top soil (pupuk + tanah merah + sekam + pasir) AREA 2	m3	8,38	220.000	Rp	1.843.600	
	Top soil (pupuk + tanah merah + sekam + pasir) AREA 3	m3	12,25	220.000	Rp	2.695.000	
0	Top soil (pupuk + tahan meran + sekam + pasii) AREA 3	1113	12,25	220.000	Kþ	2.095.000	
	Sub Total A				Rp	15.583.600	
II	Penanaman Pohon (include steger)						
1	Tabebuea pink daun besar						
	dia. batang 7-8cm, tinggi : 4m (overall)						
	AREA 1	phn	92	510.000	Rp	46.920.000	
	AREA 2		67	510.000	Rp	34.170.000	
	AREA 3		95	510.000		48.450.000	
2	Trembesi						
_	dia. batang 10-12cm, tinggi : 4m (overall)						
	AREA 1	Phn	2	600.000	Rp	1.200.000	
		Pnn	2		•		
	AREA 3		3	600.000	Rp	1.800.000	
3	Glodokan tiang (Polyalthia Longifolia)	phn	12	530.000	Rp	6.360.000	
3	dia. batang 3-4cm, tinggi : 4m (overall)	ріші	12	330.000	ТЪ	0.500.000	
	dia. Datang 3-4011, tinggi . 4111 (Overall)						
	Sub Total B				Rp	138.900.000	
	Jun Total D				Λþ	130.900.000	
III	PERAWATAN 3 BULAN TERMASUK PENYIRAMAN	bln	3,00	4.000.000	Rn	12.000.000	
l'''	Sub Total C	DIII	3,00	4.000.000		12.000.000	
	Sub Total C				Rp	12.000.000	
		1 /					

REKAPITULASI

Α	Pekerjaan Persiapan	Rp	15.583.600
В	Penanaman Pohon (include steger)	Rp	138.900.000
С	PERAWATAN 3 BULAN TERMASUK PENYIRAMAN	Rp	12.000.000
	Sub total 1	Rp	166.483.600
	PPn 10 %	Rp	16.648.360
	TOTAL	Rp	183.131.960

Bogor, 12 Maret 2020 CV. Fundada Lanscape

Pendi B. Asim Direktur