RENCANA ANGGARAN BIAYA

PEKERJAAN : PAGAR KAWASAN KAVLING BLOK CG 01 - CG 02 & PAGAR BELAKANG KAVLING BLOK CG 00

LOKASI : BUKIT TERATAI - CITRAINDAH CITY

NO	URAIAN	SAT	VOLUME	HARSAT	JUMLAH	KETERANGAN
A	PEKERJAAN PERSIAPAN					
II	Bouwplank	m1	320,69	6.500	2.084.485	
II	Direksi Keet	Ls	1,00	1.400.000	1.400.000	
3	Air kerja dan Listrik Kerja	Ls	1,00	1.700.000	1.700.000	
4	Keamanan	Ls	1,00	1.400.000	1.400.000	
	Sub Total A				6.584.485	
В	PEKERJAAN PAGAR KAWASAN BLOK CG 01 - CG 02					
II	Sloof uk. 15/15 (1:2:3)	m3	7,22	2.300.000	16.606.000	
II	Kolom uk. 15/15 (1:2:3)	m3	3,18	2.300.000	7.314.000	
3	Ring balok uk. 13/13 (1:2:3)	m3	5,42	2.300.000	12.466.000	
4	Pasangan batako (1:5)	m2	423,31	80.000	33.864.800	
5	Nat batako (1 sisi dalam)	m1	320,69	18.000	5.772.420	
6	Ban - banan Kolom (1 sisi dalam)	m1	171,20	25.000	4.280.000	
7	Plester + acian (1 sisi luar)	m2	831,91	90.000	74.871.900	
	Sub Total B				155.175.120	
С	PEKERJAAN PAGAR BELAKANG KAVLING BLOK CG 00					
1	Galian pondasi batu kali	m3	80,17	85.000	6.814.450	
2	Urugan tanah kembali (include pemadatan)	m3	16,03	50.000	801.500	
3	Pondasi batu kali	m3	64,14	700.000	44.898.000	
4	Sloof uk. 15/15 (1:2:3)	m3	7,22	2.300.000	16.606.000	
5	Kolom uk. 15/15 (1:2:3)	m3	1,25	2.300.000	2.875.000	
6	Ring balok uk. 13/13 (1:2:3)	m3	5,42	2.300.000	12.466.000	
7	Pasangan batako (1:5)	m2	166,76	80.000	13.340.800	
8	Plester + aci (1 sisi luar)	m2	256,55	90.000	23.089.500	
	Sub Total C				120.891.250	

REKAPITULASI

Α	PEKERJAAN PERSIAPAN	6.584.485
В	PEKERJAAN PAGAR KAWASAN BLOK CG 01 - CG 02	155.175.120
С	PEKERJAAN PAGAR BELAKANG KAVLING BLOK CG 00	120.891.250
	Sub total 1	282.650.855
	Fee Kontraktor	28.265.086
	Sub total 2	310.915.941
	DIBULATKAN	310.915.000
	PPn 10 %	31.091.500
	TOTAL	342.006.500